Pipes supplied but found not to be of good quality will be rejected and the supplier shall remove the same and shall guarantee to replace the same with fresh ones then and there.

If the successful competitor fail to supply the pipes or replace the rejected pipes in time the same will be purchased elsewhere and difference in cost between the rate tendered and that at which the pipes are purchased will be debited to his accounts.

List of pipes required for Maralwady Tank Works.

Description	Per	Quantity	Rate	Remarks
2" Galvanized iron pipes ...	R. ft.	800		

C. VIJAYARANGAM NAIDU,
Executive Engineer.

TUMKUR DIVISION.

Dated 4th March 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 18th March 1918, for constructing additional rooms to Anglo-Vernacular School at Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M., except on Sundays and holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (350) three hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing additional rooms to Anglo-Vernacular School" at Tumkur, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for extending the Anglo-Vernacular School at Tumkur.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement ...	C. yd.	281
2	Burnt stone in mortar ...	C. ft.	10,874
3	Burnt brick in mortar ...	"	10,175
4	Burnt stone slabs ...	S. ft.	1,700
5	Teakwood doors with panelled shutter and iron works, etc., complete ...	"	208
6	Teakwood windows with iron bars with both panelled and glazed shutters ...	"	299
7	Teakwood ventilators with iron bars and glazed shutters ...	"	105
8	Chunam plastering ...	Sqr.	144·16
9	White and colourwashing ...	"	144·16
10	Providing burnt stone pillars with 7"×7" base and capitals complete ...	No.	28
11	Teakwood work wroght and put up ...	C.ft.	462·00
12	Roofing with 1st Class Mangalore tiles on teak reepers, etc., complete ...	Sqr.	63·06
13	*Ridge* tiles set in mortar ...	R. ft.	132
14	Cornice 1½' deep including plastering ...	"	265
15	Cornice 9" deep including plastering ...	"	84
16	Coping with brick in mortar including plastering ...	"	70
17	Ornamental eave board ...	"	266
18	Zinc sheet for the valley 3' breadth over 1" teak planks ...	S. ft.	75
19	Flooring with Cudapah slabs over 3" concrete bed and cement pointing ...	Sqr.	33·34
20	Chaculate painting ...	"	9·58
21	Wood oiling ...	"	6·02
22	Dwarf wall heavy over gable ends ...	R. ft.	56
23	Dwarf wall light ...	"	40
24	Clearing site and levelling ground ...	Lump sum	rupees
	Old building.		
25	Teakwood panelled doors with iron works, etc., complete ...	S. ft.	28
26	Removing window and inserting door, etc., with repairs ...	No.	1
27	Removing Buttresses and repairs, etc. ...	Lump sum	rupees.

Dated 28th February 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 20th March 1918, for constructing Anglo-Vernacular School as per No. 5, Type Design at Pavagada. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M. except on Sundays and holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Anglo-Vernacular School at Pavagada," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Tumkur, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing an Anglo-Vernacular School Building as per type plan D. No. 5 at Pavagada.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement	C. yd.	87
2	Burnt stone in clay	C. ft.	3,186
3	Burnt brick in clay	"	3,055
4	Burnt brick in chunam	"	742
5	Archwork	"	45
6	Burnt stone slabs moderately dressed	S. ft.	498
7	Burnt stone slabs neatly dressed	"	52
8	Cutting grooves to stone pillars	Each	8
9	Corbels below cill slabs of windows	"	8
10	Chunam plastering	Sqr.	74·17
11	White and colourwashing	"	74·17
12	Honne wood work wrought and put up with wood oiling	C. ft.	166·0
13	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete	Sqr.	35·55
14	Ridge tiles set in mortar	R. ft.	141
15	Chunam borders at gable ends	"	84
16	Flooring with Cuddapah slabs over 3" concrete and cement pointing	Sqr.	20·25
17	Teakwood ornamental cave boards	R. ft.	303
18	Honne wood battened doors with the iron clamps and iron works, etc., complete	S. ft.	263
19	Honne wood battened windows with ½" iron bars and clamps, etc., complete	"	165
20	Honne wood panelled windows with ½" iron bars and clamps including semi-circular top, complete	"	101
21	Masonry windows at the sides of front windows as per plan	Each	4
22	Thin cornice or moulding over front windows	R. ft.	85
23	Chunam pointing	Sqr.	3·92
24	Turning wood work	Lump	sum
25	Ventilating tiles	Each	18
26	Carving corners of the rooms	Lump	sum
27	Zinc sheet for the valleys	S. ft.	192
28	Teak planking below the sheets	"	192
29	Chocolate painting	Sqr.	14·31
30	Clearing site and levelling ground	Lump	sum
31	Deviation of road	Lump	sum

N. G. KRISHNAIENGAR,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification.

The attention of the public is invited to page 216 of the *Mysore Gazette*, dated 7th March 1918, calling for tenders for constructing a Local Fund Dispensary and In-patient ward with out-houses at Challakere, Chitaldrug District. The last date for tendering is 20th March 1918.

N. ANANDALWAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

EDUCATION DEPARTMENT.

Abstract Notification, dated 7th March 1918.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, dated 7th March 1918, calling for tenders for the supply of 50 sets of carpentry tools required for the Education Department.

C. R. REDDY,
Offg. Inspector-General of Education.